

KEEFE GENERAL SERVICES
Asphalt Paving
 24 Tacoma Street
 CRANSTON RHODE ISLAND 02920
 (401) 942-1904

No **0136**

PROPOSAL SUBMITTED TO 100 Bosworth St. Realty Co.		PHONE 647-7660	DATE 8-18-92
STREET 46 Kent View Dr.		JOB NAME Excavation for tank removal	
CITY, STATE AND ZIP CODE Hope, RI 02831		JOB LOCATION 100 Bosworth St. Prov, RI 02909	
ARCHITECT Pete Maggiacomo	DATE OF PLANS 8-01-92	JOB PHONE 0	

We hereby submit specifications and estimates for:

Dear Peter,

As you know we excavated the oil tank on the site mentioned above, we followed your instructions to dig south of the trench to see how close the tank was to the boiler room wall, as we excavated we found the end of the tank to be approximately Six (6') from where we started, which leads to suspect that the length of the tank is positioned in an east west direction, the tank size being 10'-6" wide & 23'-2" long. I measured the area placing the north end of the tank approximately 3-1/2' from the north wall of the building and I need at least 3' (+) for the bucket of the excavator to dig, leaving me with no room to work with.

Therefore if I have to dig out the tank, I will not guarantee that it will not damage the foundation or wall of the building. If you want me to continue to dig out the tank, than I will ask you to sign a liability release form to exempt me from any law suits that may arise if the wall lets go, and creates considerable damage to the building.

P.S. It is my strong belief that if I dig out the tank there will be no support to the foundation and it may cause heavy damages to the building.


Very Truly Yours,
 John R. Keefe

We Propose hereby to furnish material and labor — complete in accordance with above specifications, for the sum of:

Payment to be made as follows: **Net 20 Days** _____ dollars (\$ _____).

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workmen's Compensation Insurance.

Authorized Signature



Note: This proposal may be withdrawn by us if not accepted within **30** days.

Acceptance of Proposal — The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date of Acceptance: _____

Signature _____

Signature _____

RHODE ISLAND DEPARTMENT OF ENVIRONMENTAL MANAGEMENT
DIVISION OF GROUNDWATER
COMPLAINT REPORT

No.:

City or Town: Prov

Assigned to:

Complaint Received: Date: 7/31/92 Time: 0900 Rec'd by: Shul

Name and Address of Complainant:

Name and Address of Alleged Source:

100 Bosworth St
Prov.

Telephone No.:

Telephone No.:

Name Disclosure Permission: _____

Nature of Complaint: Meeting on Site

Impact:

INVESTIGATOR'S REPORT

Summary:

Met owner R. Maggiorano + M. Del Rossi - RE

1) 10,000 gallon tank passed

2) 2nd Tank unknown
is structurally impounded?
to open

3) expose tank - check
level of contamination

4) Sample of GZ-5 (greater than
1'0" product with ORS probe

Investigator:

Shul

Date:

7/31/92